

Royalty Statement for the work of: Construction of Ward office in Ward No.05, Byatarayanapura (Third and Final Bill)

Sl.No	Particulars	Unit	Quantity	Gravel/ Solid block/ SSM		Sand		Remarks
				Constant	Quantity	Constant	Quantity	
1	Plain Cement Concrete of mix 1:2:4	Cum	4.80	0.88	4.22	0.53	2.54	
2	Plain Cement Concrete of mix 1:4:8	Cum	3.44	0.85	2.92	0.57	1.96	
3	size stone masonry in foundation cement mortar 1:6	Cum	20.60	1.05	21.63	0.28	5.77	
4	18mm thick cement plaster in single coat with cement mortar 1:4	Sqm	63.46			0.02	1.27	
Total					28.78		11.54	

Material	Quantity	Rate	Amount
Size Stone	0.00	184.00	0.00
Jelly / Metal	28.78	126.00	3626.03
Sand	11.54	138.00	1592.80
Total			5218.82

[Signature]

[Signature]

Asst. Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore - 92